Clay County, Missouri
Land Survey Document

ROUTE	STATE	DISTRICT	SHEET NO.
92	MO	4	7

JOB NO. J4P1537
CONTRACT ID
PROJECT NO.
COUNTY CLAY
DATE 10-2-03

Affinis

Coordinate Point Listing
Missouri Coordinate System of 1983

Reciprocal Average Grid Factor : 1.0000917

SHEET NO.	STATION (1)	LOCATION	NORTHING (FEET)	EASTING (FEET)	DESCRIPTION
ROUTE 92 CENTERLINE					
3	578+99.57	BOP	1165752.64	2823018.46	BEGIN CONSTRUCTION
5	605+45.13	PI	1165776.87	2825663.92	NO CURVE
RAMP 2 BASELINE					
4-5	8+56.17	BOP	1165773.71	2825318.80	= STA 602+00 ROUTE 92 CENTERLINE
4-5	11+00.00	EOP	1165562.46	2825173.90	
RAMP 3 BASELINE					
3	9+00.00	BOP	1165953.31	2824941.53	= STA 597+00 ROUTE 92 CENTERLINE
3	11+21.31	EOP	1165769.13	2824613.82	

1 Ground Distance
NOTE: The reciprocal of the average grid factor is used as a mulitplier from state plane distance to ground distance.

730 Series
4/8/04 DM

ROUTE 92
COORDINATE POINT SHEET
SHEET 1 OF 1

http://www.ClayCoGov.com