Clay County, Missouri
Land Survey Document

ROUTE	STATE	DISTRICT	SHEET NO.
92	MO	4	7

JOB NO. J4P1116
CONTRACT ID.
PROJECT NO.
COUNTY CLAY
DATE 9/8/05

Coordinate Point Listing
Missouri Coordinate System of 1983

Reciprocal Average Grid Factor : 0.9999091

SHEET NO.	STATION[1]	LOCATION	OFFSET	NORTHING	EASTING	DESCRIPTION	DESIGN PT. ID
3	740+00.00	RTE 92	0	1,165,849.60	2,839,096.21	POT	
3	744+82.87	RTE 92	0	1,165,856.89	2,839,579.03	PC	
4	748+96.64	RTE 92	69.24	1,165,863.14	2,839,992.75	PI	
4	752+79.85	RTE 92	0	1,166,122.78	2,840,314.92	PT	
5	765+71.83	RTE 92	0	1,166,933.50	2,841,320.87	PC	
5	768+58.23	RTE 92	40.20	1,167,113.22	2,841,543.87	PI	
5	771+29.70	RTE 92	0	1,167,383.74	2,841,637.92	PT	
5	775+00.00	RTE 92	0	1,167,733.50	2,841,759.52	POT	
3 & 4	0+00.00	BYPASS -W	0	1,165,850.61	2,839,163.02	PC	
3 & 4	0+33.19	BYPASS -W	1.10	1,165,851.11	2,839,196.20	PI	
3 & 4	0+66.28	BYPASS -W	0	1,165,855.99	2,839,229.03	PT	
3 & 4	2+26.89	BYPASS -W	0	1,165,879.62	2,839,387.90	PC	
3 & 4	2+60.08	BYPASS -W	1.10	1,165,884.51	2,839,420.72	PI	
3 & 4	2+93.17	BYPASS -W	0	1,165,885.01	2,839,453.91	PT	
3 & 4	4+17.85	BYPASS -W	0	1,165,886.89	2,839,578.58	PC	
3 & 4	5+24.00	BYPASS -W	4.80	1,165,888.49	2,839,684.71	PI	
3 & 4	6+29.56	BYPASS -W	0	1,165,909.14	2,839,788.82	PT	
3 & 4	6+45.22	BYPASS -W	0	1,165,912.19	2,839,804.18	PC	
3 & 4	6+78.99	BYPASS -W	1.14	1,165,918.76	2,839,837.31	PI	
3 & 4	7+12.67	BYPASS -W	0	1,165,920.82	2,839,871.02	PT	
3 & 4	7+26.11	BYPASS -W	0	1,165,921.64	2,839,884.44	PC	
3 & 4	8+28.77	BYPASS -W	10.43	1,165,927.89	2,839,986.91	PI	
3 & 4	9+28.62	BYPASS -W	0	1,165,974.02	2,840,078.63	PT	

Coordinated Point Sheet
Sheet 1 of 2

1 Ground Distance

NOTE : The reciprocal of the average grid factor is used as a multiplier from state plane distance to ground distance.

REV.

P:\de-proj\Clay\J4P1116\plan_sheets\100_e\J4P1116_coord_point.dgn 10:43:24 AM 09/07/2005

Hwy Dept
4/12/07 DM

http://www.ClayGov.com