92	MO	4	8
JOB NO. J4P1116			
CONTRACT ID.			
PROJECT NO.			
COUNTY CLAY			DATE 9/8/05

Coordinate Point Listing
Missouri Coordinate System of 1983

Reciprocal Average Grid Factor : 0.9999091

SHEET NO.	STATION[1]	LOCATION	OFFSET	NORTHING	EASTING	DESCRIPTION	DESIGN PT. ID
5 & 6	0+00.00	BYPASS-E	0	1,166,989.04	2,841,384.15	PC	
5 & 6	0+60.90	BYPASS-E	5.26	1,167,032.07	2,841,427.25	PI	
5 & 6	1+20.60	BYPASS-E	0	1,167,087.12	2,841,453.28	PT	
5 & 6	1+52.03	BYPASS-E	0	1,167,115.54	2,841,466.72	PC	
5 & 6	1+73.43	BYPASS-E	0.65	1,167,134.89	2,841,475.87	PI	
5 & 6	1+94.78	BYPASS-E	0	1,167,152.98	2,841,487.31	PT	
5 & 6	2+43.66	BYPASS-E	0	1,167,194.29	2,841,513.43	PC	
5 & 6	3+55.35	BYPASS-E	6.41	1,167,288.69	2,841,573.12	PI	
5 & 6	4+66.06	BYPASS-E	0	1,167,394.18	2,841,609.80	PT	
5 & 6	5+98.82	BYPASS-E	0	1,167,519.58	2,841,653.39	PC	
5 & 6	6+36.05	BYPASS-E	1.38	1,167,554.75	2,841,665.62	PI	
5 & 6	6+73.14	BYPASS-E	0	1,167,587.71	2,841,682.92	PT	
5 & 6	8+01.23	BYPASS-E	0	1,167,701.14	2,841,742.43	PC	
5 & 6	8+38.45	BYPASS-E	1.38	1,167,734.10	2,841,759.73	PI	
5 & 6	8+75.54	BYPASS-E	0	1,167,769.26	2,841,771.95	PT	

1 Ground Distance

NOTE : The reciprocal of the average grid factor is used as a multiplier from state plane distance to ground distance.

Coordinated Point Sheet
Sheet 2 of 2

T:\de-proj\Clay\J4P1116\plan_sheets\100_e\J4P1116_coord_point_2.dgn 10:44:07 AM 09/07/2005

Hwy. Dept.
4/12/07 LM

Clay County, Missouri
Land Survey Document

http://www.ClayCoGov.com